

3D perception Compact SX+62



Brief Introduction

Beta 2.5

The Compact SX+62 BrilliantColor DLP has 3100 Ansi lumens, a contrast of 7500:1 and an SXGA+ 1400 x 1050 resolution. With the lens shift function, the projector can be positioned very freely. 485 cm image width, the projector will be able to illuminate well. However, if room light is available, the image width should ideally not exceed 323 cm. The model was built by 3D perception in 2009 and is no longer current, but is still very popular in our projector database.

Display Type

1 x DLP Chip
SXGA 4/3 Ti Digital Light Processing Chip

Ansi-Lumen

3100

1033 Lux (bei 200 cm Screen)

Contrast

7500:1 full on/off

7500:1 full on/off

Black Level

0,4133 min. Lumen

0,138 min. Lumen

Lens shift

Vert.: +/-55% Hori.: +/-45%

Resolution

SXGA+ 1400 x 1050

1.470.000 Pixel

UXGA 1600 x 1200 compressed

Video Modes

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Application

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Medium screen width or rooms with a little more ambient light, max. 200 lumens.

Light Source

2 x 300W UHP Lamp

Light Life

2000 h. 5000 h. in Eco Mode

Operating Costs

-

Focus

Powered

Zoom

Powered 1,25

Objective

F=2,1-6,5 f=34,1-42,7 mm

Throw Ratio

1,7-2,5:1

Audio

No

Connections

DVI-D mit HDCP in
5 x BNC RGBHV in
YUV in
Cinch Video in
RJ45 in
RS232C Din 9pin in
USB in
12V Trigger

Ceiling Mounting

Yes

Power


1050W

Size WxHxD

510 x 223 x 376 mm (20,1"x8,8"x14,8") 42,76 L/dm³

Operating Noise

30 dB in Eco Mode



Weight

12,60 kg / 27,78 lbs.

Keystone

Vert.: +/-30°
Hori.: +/-15°

Illumination

-

Frequenz
H-sync: 15-150 kHz
V-sync: 48-190 Hz
Range max.: 205 MHz

Foot-Lamberts
96 fL / max. 485 cm screen width

329 cd/m²

- Features
- Lens shift Funktion
 - Eco Mode
 - BrilliantColor™
 - Remote control with backlight
 - Lan network compatible.

Optional	Object lens original	R9801209 / EN14
	Object lens original	R9801214 / EN11
	Object lens original	R9801218 / EN12
	Object lens original	R9801225 / EN15
	Object lens original	R9801228 / EN13
	Object lens original	R9801249 / EN16

Order here: <https://www.hcinema.de/lampen/shop-en.php?id=hc1570>

Optional Lenses					
Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
EN16	4.1-7.1:1	8.2-14.2 m	+/-55%	+/-45%	Powered
EN14	2.56-4.1:1	5.1-8.2 m	+/-55%	+/-45%	Powered
EN13	1.3-1.7:1	2.6-3.4 m	+/-55%	+/-45%	Powered
EN11	1.74-2.51:1	3.5-5 m	+/-55%	+/-45%	Powered
Fix Optional Lenses					
EN15	1.25:1	2.5 m	+/-55%	+/-45%	No Zoom
EN12	0.84:1	1.7 m	0.0% Fix		No Zoom

Status
Data
2009 Discontinued (EOL) // Last update of the data: 2023-08-04

More Details



HCinema

<https://www.projector-database.com/pro/3dperceptioncompactsxplus62-en.html>



Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.