Acer 7765PE

Brief Introduction Beta 2.5	A brief introduction to the 7765PE: The Acer standard portable DLP projector offers 800 Ansi lumens, a contrast of 450:1 and an XGA 1024 x 768 resolution. An image width of up to 246 cm is possible as the projector has 800 Ansi lumens. However, if room light is available, the picture should be max. 164 cm wide. The model was built by Acer in 2000 and is no longer current.
Display Type	1 x 0,7" DLP Chip XGA 4/3 Ti Digital Light Processing Chip
Ansi-Lumen	Projector: 800 / Screen: 259 Lux (bei 203 cm Screen)
Contrast	Projector: 450:1 full on/off / Screen: 450:1 full on/off
Black Level	Projector: 1,7778 min. Lumen / Screen: 0.58 min. Lumen
Offset	-
Resolution	XGA 1024 x 768 786.432 Pixel SXGA 1280 x 1024 compressed
Video Modes	NTSC PAL SECAM
Application	Standard-Portabel | External training and company presentations, as well as product presentations. Small screen width, rooms with very little ambient light below 100 lumens.
Light Source	150W NSH Lamp Articel Nr.: 60.J1720.001
Light Life	1500 h.
Operating Costs	-
Focus	Manual
Zoom	Manual 1,29
Objective	F=2,8-3,1 f=31-40 mm
Throw Ratio	2,18-2,81:1
Audio	1 x 1W
Connections	Eingänge 1 x RGB 15 pol. Mini-Sub-D 1 x Line in Stereo Klinke 3,5mm (AV-BOX) 1 x RCA Composite Video (AV-BOX) 1 x S-Video Mini Din 4 pin (AV-BOX) 1 x RCA Stereo (AV-BOX) Ausgänge 1 x Stereo Klinke 3,5mm (AV-BOX) Schnittstellen 1 x 8-pin Mini DIN für MS seriell und PS/2 Maus der optionalen AV-Box videotauglich. TV-Box (optional)
Ceiling Mounting	Yes
Power	250W
Size WxHxD	198 x 62 x 243 mm (7,8"x2,4"x9,6") 2,98 L/dm³
Operating Noise	40dB
Weight	2,30 kg / 5,07 lbs.
Keystone	Vertical
Illumination	-



Frequenz	H-sync: 20,0-88,0 kHz V-sync: 20-100 Hz
Foot-Lamberts	24 fL / max. 246 cm screen width
	82 cd/m²
Features	■ Freeze ■ Remote control with laser pointer ■

Optional

Bulb only Osram	NLMP208
Lamp ruby	Ruby-LMP208
Lamp original	60.J1720.001
Remote original	MC.JMV11.00G

Order here: https://www.hcinema.de/lampen/shop-en.php?id=n4877

Status Data: 2000 Discontinued (EOL) // Last update of the data: 2023-08-04

More Details: HCinema https://www.projector-database.com/pro/acer7765pe-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.