

Anders + Kern AstroBeam S150



ANDERS + KERN ASTROBEAM S150



Brief Introduction

Beta 2.5

A brief introduction to the AstroBeam S150: The Anders + Kern standard portable LCD projector offers 1300 Ansi lumens, a contrast of 300:1 and an SVGA 800 x 600 resolution. 1300 Ansi lumens ensure that a picture width of 314 cm is also possible. However, if room light is available, the picture should be max. 209 cm wide. The model was built by Anders + Kern in 2004 and is no longer current, but is still a popular projector in our database.

Display Type



3 x 0,7" LCD TFT Panel
SVGA 4/3 Liquid Crystal Display

Ansi-Lumen

1300

433 Lux (bei 200 cm Screen)

Contrast

300:1 full on/off

300:1 full on/off

Black Level

4,3333 min. Lumen

1,458 min. Lumen

Offset

Resolution

SVGA 800 x 600
480.000 Pixel
SXGA 1280x1024 compressed

Video Modes

SECAM, NTSC,
Standard-Portabel | External training and company presentations, as well as product presentations.

Application

Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

165W EHPL Lamp
Articel Nr.: 21600

Light Life

2000 h.

Operating Costs

30,95% / 0,13 €

Focus

Manual

Zoom

Manual 1,23

Objective

F=1,7-2,1 f=26-32 mm

Throw Ratio

1,65-2,05:1

Audio

2W Mono

Connections

D-sub 15pin in
YUV in
Cinch Video in
Cinch Stereo in
S-Video in
Mini jack in
RS232C Din9 pin

Ceiling Mounting

Yes

Power

210W

Size WxHxD

233 x 93 x 297 mm (9,2"x3,7"x11,7") 6,44 L/dm³

Operating Noise

37dB

Weight


3,10 kg / 6,83 lbs.

Keystone

Vertical

Illumination

85%



Foot-Lamberts

40 fL / max. 314 cm screen width

137 cd/m²

- Features
- Freeze

■ Picture-in-Picture

■ Remote control with laser pointer und mouse control

■

Optional

Bulb only	NLMPf6353
Lamp original	21600
Universal Remote original	Fernb-uni-V3

Status Data

Order here: <https://www.hcinema.de/lampen/shop-en.php?id=nf339>
2004 Discontinued (EOL) // Last update of the data: 2023-08-04

More Details



HCinema

<https://www.projector-database.com/pro/akastrobeams150-en.html>