ASK Proxima C520

3LCD | Edge Blending | Lens Shift | Netzwerk | USB

Brief Introduction Beta 2.5	The ASK Proxima model C520 is an LCD projector with XGA 1024 x 768 resolution and a contrast of 5000:1. The built-in lens shift and keystone correction function provides freedom when setting up. An image width of up to 646 cm is possible as the projector has 5500 Ansi lumens. The projector can create rooms with residual light with a smaller image width, we recommend a maximum of 431 cm. If the image is still too small, the integrated edge blending software can help to project a larger image with additional projectors. The model was built by ASK Proxima in 2014 and is no longer current.
Display Type	3 x 0,63" LCD TFT Panel XGA 4/3 Liquid Crystal Display
Projector: Ansi-Lumen	5500
Projector: Contrast	5000:1 full on/off
Projector: Black Level	1,1000 min. Lumen
Screen	1833 Lux (bei 200 cm Screen) 5000:1 full on/off 0,367 min. Lumen
Lens shift	Vert.: +/-40% Hori.: +/-10%
Resolution	XGA 1024 x 768 786.432 Pixel UXGA 1600 x 1200 compressed
Video Modes	Pal, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p
Application	Standard-Portabel | External training and company presentations, as well as product presentations. Wide screen width or rooms with plenty of light (over 200 lumens).
Light Source	280W Lamp
Light Life	3000 h. 4000 h. in eco Mode
Operating Costs	-
Focus	Manual
Zoom	Manual 1,65
Objective	F=1,6-2,08 f=19,36-31,94 mm
Throw Ratio	1,51-2,5:1
Audio	10W
Connections	HDMI in 2 x D-sub 15pin in 1 x out Cinch Video in S-Video in Mini Jack Audio in und out USB in RS232C Din 9 pin in RJ45 in
Ceiling Mounting	Yes
Power	375W
Size WxHxD	385 x 110 x 308 mm (15,2"x4,3"x12,1") 13,04 L/dm³
Operating Noise	36 / 32 dB in Eco Mode
Weight	4,85 kg / 10,69 lbs.
Keystone	Vert.: +/-30° Hori.: +/-15°
Illumination	80%



ASK PROXIMA C520

Frequenz	H-sync: 15-100 kHz V-sync: 48-85 Hz
Foot-Lamberts	170 fL / max. 646 cm screen width 582 cd/m²
Features	■ Lens shift Funktion ■ User logo ■ Eco Mode ■ Kensington Slot ■ Edge Blending ■ Lan network compatible.
Status	2014 Discontinued (EOL) // Last update of the data: 2023-08-04
Data	Created: 2014-08-20 14:04:44
More Details	https://www.projector-database.com/pro/askproximac520-en.html



Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.