

ASK Proxima M2



ASK PROXIMA M2



Brief Introduction

Beta 2.5

A brief introduction to the M2: The ASK Proxima DLP projector offers 1400 Ansi lumens, a contrast of 1100:1 and an XGA 1024 x 768 resolution. The projector can illuminate an image width of up to 326 cm with its 1400 Ansi lumens. In room light, however, the image width should ideally be less than 217 cm. The model was built by ASK Proxima in 2004 and is no longer current, but is still very popular in our projector database.



1 x 0,7" DLP Chip

XGA 4/3 Ti Digital Light Processing Chip

Display Type

Ansi-Lumen

1400

453 Lux (bei 203 cm Screen)

Contrast

1100:1 full on/off

1100:1 full on/off

Black Level

1,2727 min. Lumen

0.413 min. Lumen

Offset

Resolution

XGA 1024 x 768

786.432 Pixel

SXGA 1280 x 1024 compressed

Video Modes

NTSC 3.58, NTSC 4.43, PAL (all), SECAM (all), SDTV (480i), EDTV (480p)

Application

Micro-Portabel | Small mobile presentations..

Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

120W UHP Lamp

Light Life

3000 h.

Operating Costs

-

Focus

Manual

Zoom

Manual 1,27

Objective

F=2,0-2,2 f=26-33 mm


Throw Ratio

1,85-2,35:1

Audio

1W

1 S-video, 1 composite video, 1 DVI connector, audio line in



Connections



Ceiling Mounting

-

Power

155W

Size WxHxD

199 x 63,4 x 148 mm (7,8"x2,5"x5,8") 1,86 L/dm³

Operating Noise

32dB

Weight

1,10 kg / 2,43 lbs.

Keystone

Vert.: +/-15°

Illumination

-

Frequenz


H-sync: 15-100 kHz

V-sync: 43,5-130 Hz

Foot-Lamberts

42 fL / max. 326 cm screen width

144 cd/m²



- Freeze
 - Kensington Slot
 - Warping
 - Picture-in-Picture
 - Remote control with laser pointer und mouse control
- 2004 Discontinued (EOL) // Last update of the data: 2023-08-04

Features

Status
Data

More Details



HCinema

<https://www.projector-database.com/pro/askproximam2-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.