
Enthronic E976M



Brief Introduction Beta 2.5	With the E976M, manufacturer Enthronic offers an LCD projector with XGA 1024 x 768 resolution and a contrast of 400:1. 2600 Ansi lumens ensure that a picture width of 444 cm is also possible. However, if room light is available, the picture should be max. 296 cm wide. The model was built by Enthronic in 2005 and is no longer current.
Display Type	3 x 0,7" LCD TFT Panel XGA 4/3 Liquid Crystal Display

	Projector		Screen
Ansi-Lumen	2600		867 Lux (bei 200 cm Screen)
Contrast	400:1 full on/off		400:1 full on/off
Black Level	6,5000 min. Lumen		2,184 min. Lumen
Offset			

Resolution	XGA 1024 x 768 786.432 Pixel
Video Modes	PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p
Application	Standard-Portabel | External training and company presentations, as well as product presentations. Medium screen width or rooms with little light, max. 100 lumens.
Light Source	180W Lamp
Light Life	-
Operating Costs	-
Focus	Manual
Zoom	Manual
Objective	-
Throw Ratio	-
Audio	1 x 1,5W



Connections	DVI D-sub 15pin in Cinch Video in S-Video in
Ceiling Mounting	Yes
Power	-
Size WxHxD	320 x 90 x 220 mm (12,6"x3,5"x8,7") 6,34 L/dm³
Operating Noise	-
Weight	2,90 kg / 6,39 lbs.
Keystone	Vert.: +/-15°
Illumination	85%
Frequenz	H-sync: 15,63-91 kHz V-sync: 50-100 Hz
Foot-Lamberts	81 fL / max. 444 cm screen width 278 cd/m²
Features	-
Status	2005 Discontinued (EOL) // Last update of the data: 2023-08-04
Data	

ENTHRONIC E976M

More Details

HCinema

https://www.projector-database.com/pro/enthronice976m-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.