

# Epson EB 595WI

EPSON EB 595WI



The Epson EB 595WI LCD projector has 3300 Ansi lumens, a contrast of 10000:1 and a WXGA 1280 x 800 resolution. The lamp in the projector is specified with a lamp life of 4000 hours, which is over 5.5 years with a daily viewing time of 2 hours. The integrated media player can play files directly. An image width of up to 584 cm is possible as the projector has 3300 Ansi lumens. However, if room light is available, the picture should be max. 389 cm wide. The projector also offers a whiteboard function that makes training and presentation rooms interactive. The model was built by Epson in 2014 and is no longer current, but is still very popular in our projector database.



3 x LCD TFT Panel

WXGA 16/10 Liquid Crystal Display

Projector	3300 / 1900 im Eco Mode	Screen	1320 Lux (bei 200 cm Screen)
Contrast	10000:1 full on/off		10000:1 full on/off
Black Level Offset	0,3300 min. Lumen		0,132 min. Lumen

Resolution  
WXGA 1280 x 800  
1.024.000 Pixel

Video Modes  
Pal, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

**Media player formats:** .jpg .bmp .gif .png .avi

Application  
Whiteboard | Training and company presentations, as well as product presentations.

Medium screen width or rooms with a little more ambient light, max. 200 lumens.

Light Source  
-  
Articel Nr.: ELPLP80 / V13H010L80

Light Life  
4000 h. 6000 h. in eco Mode

Operating Costs  
-

Focus  
Manual

Zoom  
No Zoom

Objective  
F=1,8 f=3,71mm

Throw Ratio  
0,27:1

Audio  
16W

Connections  
2 x HDMI in  
2 x D-sub 15pin in und out  
USB Typ A,B  
RS232C Din 9 pin in  
Mini Jack Audio in und out  
RJ45 in

Ceiling Mounting  
Yes

Power  
358 / 270W ImEco Mode


Size WxHxD  
367 x 155 x 375 mm (14,4"x6,1"x14,8") 21,33 L/dm³

Operating Noise  
38 / 28 dB in Eco Mode

Weight  
5,50 kg / 11,02 lbs.

Keystone  
Vert.: +/-3°

Illumination  
-



Frequenz	-														
Foot-Lamberts	123 fL / max. 584 cm screen width  421 cd/m²														
Features	<ul style="list-style-type: none"><li>■ Integrated Mediaplayer</li><li>■ Eco Mode</li><li>■ Wi-Fi network compatible.</li><li>■ Lan network compatible.</li><li>■ Short-throw projector</li><li>■ Interactive whiteboard function with finger possible.</li></ul>														
Optional	<table><tr><td>Interactive pen top original</td><td>V12H668010 / ELPPS02</td></tr><tr><td>Interactive Pen original</td><td>V12H667010 / ELPPN04B</td></tr><tr><td>Interaktictive pen orange original</td><td>V12H666010 / ELPPN04A</td></tr><tr><td>Lamp original</td><td>ELPLP80 / V13H010L80</td></tr><tr><td>Document camera original</td><td>ELPDC21 / V12H758040</td></tr><tr><td>Air filter original</td><td>ELPAF40 / V13H134A40</td></tr><tr><td>Remote control original</td><td>1613717</td></tr></table>		Interactive pen top original	V12H668010 / ELPPS02	Interactive Pen original	V12H667010 / ELPPN04B	Interaktictive pen orange original	V12H666010 / ELPPN04A	Lamp original	ELPLP80 / V13H010L80	Document camera original	ELPDC21 / V12H758040	Air filter original	ELPAF40 / V13H134A40	Remote control original
Interactive pen top original	V12H668010 / ELPPS02														
Interactive Pen original	V12H667010 / ELPPN04B														
Interaktictive pen orange original	V12H666010 / ELPPN04A														
Lamp original	ELPLP80 / V13H010L80														
Document camera original	ELPDC21 / V12H758040														
Air filter original	ELPAF40 / V13H134A40														
Remote control original	1613717														
Status	Order here: <a href="https://www.hcinema.de/lampen/shop-en.php?id=hc1787">https://www.hcinema.de/lampen/shop-en.php?id=hc1787</a> 2014 Discontinued (EOL) // Last update of the data: 2023-08-30 Created: 2014-01-21 14:57:57														
Data															

More Details



HCinema

<https://www.projector-database.com/pro/epsoneb595wi-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.