

LaVague LV-HD151

LAVAGUE LV-HD151



With the LV-HD151, manufacturer LaVague offers an LCD LED projector with WVGA 800 x 480 resolution and a contrast of 1000:1. Thanks to the LEDs, the projector has a light life of up to 30,000 hours, which is equivalent to over 20.5 years at 4 hours of daily use. As LaVague specifies the brightness of the projector in lumens, we have calculated an approximate ansi-lumen value in this case. 111 cm image width the projector will be able to illuminate well. If room light is available, however, the image width should ideally not exceed 74 cm. Even 1080P video signals are no problem for the projector. The model was built by LaVague in 2021 and is no longer current.

Brief Introduction

Display Type

3 x LCD Panel
WVGA 16/9 Liquid Crystal Display

Ansi-Lumen

210 / 2000 Lumen

93 Lux (200 cm Screen width)

Contrast

1000:1 full on/off

1000:1 full on/off

Black Level

0,2100 min. Lumen

0,093 min. Lumen

Offset

-

Resolution

WVGA 800 x 480
384.000 Pixel
HDTV 1920 x 1080 compressed

Video Modes

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, EDTV 480p, 576p

Application

Game-Portabel | Very portable, small-screen projections.

Light Source

LED

Light Life

30000 h.

Operating Costs

0,00 € LED

Focus

Manual

Zoom

No Zoom

Objective

-

Throw Ratio


1,45:1

Audio

Built-in loudspeaker

Connections

HDMI in
D-sub 15pin in und out
Mini Jack Audio in und out
2x USB in
Typ Cardreader: SDHC Card





Ceiling Mounting
Power
Size WxHxD
Operating Noise

Yes, is possible.
60W
208 x 80 x 165 mm (8,2"x3,1"x6,5") 2,75 L/dm³
60dB

Weight
Keystone
Illumination
Frequenz

0,98 kg / 0 lbs.
-
-
-

Foot-Lamberts

9 fL / max. 111 cm screen width
31 cd/m²

Features

- Full HD 1080P compatible
- Wi-Fi network compatible.

Screen Mirroring
Status

Optional only Chromecast / Fire TV / Apple TV / Mi Box Ads
2021 Discontinued (EOL) // Last update of the data: 2025-11-25



Data

More Details



HCinema

<https://www.projector-database.com/pro/lavaguelvhd151-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.