

Maxell MC-WU8461

MAXELL MC-WU8461



With the MC-WU8461, manufacturer Maxell offers an LCD projector with WUXGA 1920 x 1200 resolution and a contrast of 5000:1. Horizontal and vertical keystone correction makes setting up the image childs play. The projector will be able to illuminate a picture width of 787 cm. The projector can manage rooms with residual light with a smaller image width, we recommend a maximum of 525 cm. In the event that the image is still too small, the projector offers integrated edge blending software, with which several projectors can project a large image together. The model is also Full HD 1080P and 3D compatible. The model was built by Maxell in 2019 and is no longer current.

 3 x LCD TFT Panel
WUXGA 16/9 Liquid Crystal Display

Projector	6000	Screen	2667 Lux (bei 200 cm Screen)
	5000:1		5000:1
	1,2000 min. Lumen		0,534 min. Lumen

Resolution
WUXGA 1920 x 1200
2.304.000 Pixel

Video Modes
Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 3D, EDTV 480p, 576p
3D Compatibility
Frame-Packing (Full HD 3D) | Side-by-Side | Top-and-Bottom
Frame Sequential (3D Ready)

Application
Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Very large screen width and rooms with plenty of light and shaded daylight.

Light Source
365W Lamp

Light Life
Articel Nr.: DT01471

2000 h. 2500 h. in Eco Mode

Operating Costs
5,49% / 0,18 €

Focus
Powered

Zoom
Powered 2

Objective
optional

Throw Ratio
optional

Audio
2 x 8W

Connections
2 x HDMI in
D-sub 15pin in und out
Cinch Video in
Cinch Stereo in
S-Video



16/9 screen width: 200 cm
Screen: 1 Gain

Brief Introduction

Beta 2.5

Mini Jack Audio 2x in
 USB in
 RS232C Din 9 pin in
 RJ45 in
 Remote Control in und out
 HdBaseT



Ceiling Mounting

Power

Size WxHxD

Operating Noise

Yes

550W

497,8 x 134,6 x 396,2 mm (19,6"x5,3"x15,6") 26,37 L/dm³

-

Weight

Keystone

Illumination

9,21 kg / 19,84 lbs.

Vert.: +/-35°

Hori.: +/-7,5°

-

Frequenz

Foot-Lamberts

H-sync: 15-106 kHz

V-sync: 50-120 Hz


248 fL / max. 787 cm screen width

850 cd/m²

- Features
- Real Full HD 3D
 - Full HD 1080P compatible
 - Eco Mode
 - Kensington Slot
 - Warping
 - Edge Blending
 - Picture-in-Picture
 - Optional Wi-Fi network compatible.
 - Lan network compatible.
 - Crestron®-Software compatible.
 - Dicom simulation mode
 - AMX

Optional	Object lens original	UL-705
	Object lens original	SL-702
	Object lens original	ML-703
	Object lens original	LL-704
	Object lens original	FL-701
	Lamp original	DT01471

Order here: <https://www.hcinema.de/lampen/shop-en.php?id=hc146>



Optional Lenses					
Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
UL-705	5.2-8.7:1	10.4-17.4 m	50%	+/-10%	Powered
SL-702	1.3-1.9:1	2.6-3.8 m	50%	+/-10%	Powered
ML-703	1.6-3.2:1	3.2-6.4 m	55%	+/-10%	Powered

LL-704

3.1-5.2:1

6.2-10.4 m

50%

+/-10%

Powered

FL-701

0.9:1

1.8 m

0.0% Fix

No Zoom

Status

2019 Discontinued (EOL) // Last update of the data: 2023-08-04

Created: 2019-06-18 13:45:10

Data



More Details



HCinema

<https://www.projector-database.com/pro/maxellmcwu8461-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.