

Megapower ML 668



MEGAPOWER ML 668



A brief introduction to the Megapower ML 668. The DLP projector has an XGA 1024 x 768 resolution and a contrast of 2000:1. As the projector has horizontal and vertical keystone correction, the projector can be set up with plenty of free space in the room. The projector can illuminate a picture width of 289 cm well. However, if room light is available, the picture width should ideally not exceed 193 cm. The model was built by Megapower in 2006 and is no longer current.

Brief Introduction

Beta 2.5

Display Type

1 x 0,65" DLP Chip
XGA 4/3 Ti Digital Light Processing Chip

Ansi-Lumen

1100 367 Lux (bei 200 cm Screen)

Contrast

2000:1 full on/off 2000:1 full on/off

Black Level

0,5500 min. Lumen 0,184 min. Lumen

Offset

-

Resolution

XGA 1024 x 768

786.432 Pixel

SXGA 1280 x 1024 compressed

Video Modes

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

250 / 200W im Eco Mode Lamp

Light Life

2000 h. 4000 h. in Eco Mode

Operating Costs

-

Focus

Manual

Zoom

Manual 1,2

Objective

-

Throw Ratio

-

Audio

-

Connections

HDMI in
YUV in
S-Video in
Cinch Video in
12V Trigger

Ceiling Mounting

-

Power

-

Size WxHxD

333 x 123 x 295 mm (13,1"x4,8"x11,6") 12,08 L/dm³

Operating Noise

-

Weight

4,54 kg / 10,01 lbs.


Keystone

Vert.: +/-16°

Hori.: +/-7°

Illumination

-



Frequenz	H-sync: 50-85 kHz V-sync: 15-82 Hz
Foot-Lamberts	34 fL / max. 289 cm screen width 116 cd/m²
Features	■ Eco Mode
Status	2006 Discontinued (EOL) // Last update of the data: 2023-08-04
Data	

More Details



HCinema

<https://www.projector-database.com/pro/megapowerml668-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.