

Proxima DP8000

PROXIMA DP8000



Brief Introduction

Beta 2.5

The Proxima DP8000 LCD projector has 3000 Ansi lumens, a contrast of 800:1 and an XGA 1024 x 768 resolution. An image width of up to 477 cm is possible. However, the image should be smaller in room lighting. We recommend max. 318 cm. The model was built by Proxima in 2001 and is no longer current.

Display Type



3 x 1,3" LCD TFT Panel mit MLA
XGA 4/3 Liquid Crystal Display with Micro Lense Array

Ansi-Lumen

3000

971 Lux (bei 203 cm Screen)

Contrast

800:1 full on/off

800:1 full on/off

Black Level

3,7500 min. Lumen

1.218 min. Lumen

Offset

Resolution

XGA 1024 x 768

786.432 Pixel

Video Modes

SXGA 1280 x 1024 compressed

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Medium screen width or rooms with a little more ambient light, max. 200 lumens.

Light Source

270W UHP Lamp

Articel Nr.: SP-LAMP-001

Light Life

1500 h.

Operating Costs

-

Focus

Manual

Zoom

Manual 1,3

Objective

f=47-61 mm

Throw Ratio

1,75-2,24:1

Audio

2 x 2,5W Stereo mit 20W SubWoofer

Connections

2 x D sub 15pin in 1 x in

DVI-D

5 x BNC RGBHV


audio x 4 (3.5 mm stereo mini jack)

S-Video,

Cinch Video

Cinch Stereo

USB Maus, PS/2 Maus, RS232C, RJ45





Ceiling Mounting
Power
Size WxHxD
Operating Noise

Yes
400W
320 x 109 x 325 mm (12,6"x4,3"x12,8") 11,34 L/dm³
34dB

Weight
Keystone
Illumination

6,00 kg / 13,23 lbs.
Vert. +40°-15°
85%

Frequenz

H-sync: 15-100 kHz
V-sync: 43,5-130 Hz
Range max.: 165 MHz

Foot-Lamberts

90 fL / max. 477 cm screen width
308 cd/m²

Features

- Freeze
- Eco Mode
- Kensington Slot
- Remote control with laser pointer und mouse control
- Lan network compatible.
- Crestron®-Software compatible.
-



Optional Lenses

Name	Ratio	Distance	Shift V	Shift H	Zoom
Fix Optional Lenses					
Proxima LENS-016	0.9:1	1.8 m	40% Fix		No Zoom
Proxima Lens 017	4.2:1	8.5 m	40% Fix		No Zoom

Status 2001 Discontinued (EOL) // Last update of the data: 2023-08-04

Data



More Details



HCinema

<https://www.projector-database.com/pro/proximadp8000-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.