

Runco VX 1c

RUNCO VX 1C



Brief Introduction

Beta 2.5

A brief introduction to the VX 1c: The Runco DLP projector offers 1000 Ansi lumens, a contrast of 500:1 according to Ansi and an XGA 1024 x 768 resolution. The projector will be able to illuminate a picture width of 275 cm well. However, if room light is available, the picture width should ideally not exceed 183 cm. The model was built by Runco in 1998 and is no longer current. It should also be noted that, unfortunately, there are no longer any replacement lamps for the projector, neither originals nor replicas.



1 x DLP Chip
XGA 4/3 Ti Digital Light Processing Chip

Display Type

Ansi-Lumen
Contrast
Black Level
Offset

Projector 1000
500:1 nach Ansi
2,0000 min. Lumen
Screen 324 Lux (bei 203 cm Screen)
500:1 nach Ansi
0.652 min. Lumen

Resolution

XGA 1024 x 768
786.432 Pixel
SXGA 1280 x 1024 compressed

Video Modes

NTSC (NTSC/PAL International version); HDTV 480p, 1080i und 720p

Application

Stationary | Permanent installation in the training room and meeting room as well as the conference room.
Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

150W P-VIP Lamp
Articel Nr.: RUPA 003200

Light Life

1000 h.

Operating Costs

-

Focus

Powered

Zoom

Powered 1,19

Objective

-

Throw Ratio

2,0-2,37:1

Audio

-

Connections

D-sub 15pin in
S-Video in
Cinch Video in
Cinch Stereo in



Ceiling Mounting

Yes

Power

190W

Size WxHxD

370 x 146 x 470 mm (14,6"x5,7"x18,5") 25,39 L/dm³

Operating Noise


-

Weight

9,53 kg / 21,01 lbs.

Keystone

-



Illumination	-
Frequenz	-
Foot-Lamberts	30 fL / max. 275 cm screen width 103 cd/m²
Features	■ External video processor included.
Status	1998 Discontinued (EOL) // Last update of the data: 2023-08-04
Data	

More Details



HCinema

<https://www.projector-database.com/pro/runcovx1c-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.